



KUNKEL
engineering
group

107 Parallel Street
Beaver Dam, WI 53916
920.356.9447
kunkelengineering.com

March 13, 2023

Ms. Anatasia Gonstead, Clerk
City of Mayville
15 S. School Street
Mayville, WI, 53050

**Re: Letkewicz Garage Building – River Knoll Industrial Park
Site Plan Review - Amendment**

Dear Ms. Gonstead:

Our office is in receipt of plans and related documents relative to site improvements in support of the proposed Letkewicz garage building. The project was previously reviewed via letter transmitted November 1, 2022, however, was tabled at the Plan Commission meeting due to being incomplete. The proposed garage is to abut Hilltop Drive, on Lot 2 of CSM No. 7638, within the City of Mayville River Knoll Industrial Park. Please consider this transmittal a review of the site civil and architectural plans for the proposed project.

The proposed project consists of the erection of a single story 1,800 SF garage on Lot # 2, a 1-acre parcel, recently created via CSM. The parcel is zoned M-2 General Manufacturing and the proposed garage building appears compliant with the uses prescribed within that zoning classification.

Materials reviewed in conjunction with the proposed Letkewicz garage building project were prepared by JMM Consulting, LLC and consist of the following documents:

- Civil Site Plans – Six sheets
 - Existing Conditions Plan
 - Site Plan
 - Grading & Drainage Plan
 - Erosion Control Plan
 - Erosion Control Details
 - Lighting Plan

The previous submittal included an architectural plan prepared by the Drexel Team including a floor plan and building elevations. Although not included within the latest submittal, architectural details will be again addressed herein for completeness.

Note: Review documents do not include site civil plans for either signage or landscaping. Same will be required to be submitted by the owner/applicant, as appropriate, prior to the initiation of construction.

SITE SUMMARY

The proposed garage building consists of a metal structure with exterior dimension of 60 feet in length by 30 feet in width, providing a floor area of approximately 1,800 square feet. The building is set back approximately 80 feet

north of the Hilltop Drive right-of-way (ROW) due in part to the presence of an existing utility easement. A second 20-foot temporary drainage easement runs along the entire rear of the exterior dimensions of the parcel.

The grading and drainage plan reflects that stormwater drainage will be directed away from the proposed structure in westerly and northerly directions. Overall lot drainage is directed to the north via drainage swales constructed along the east and west property lines.

The proposed project will also include the extensions of both a 4-inch PVC sanitary sewer service lateral and a 1-inch water service from existing municipal utilities within the Hilltop Drive ROW. The sanitary and water laterals will serve the restroom within the proposed garage. As construction will require excavation within the Hilltop Drive ROW, the City of Mayville Utility and Public Works Directors are required to be notified, in advance, to ensure construction and street restoration are compliant with City standards.

A single driveway entrance is proposed to extend from Hilltop Drive to a parking lot fronting the proposed building. The driveway approach will be constructed of concrete pavement with an entrance width of 30-FT and a throat width of 20-FT. The parking lot has dimensions of approximately 52 FT by 72 FT with a 12-FT driveway wrapping around the west and north sides of the building. Both the parking lot and driveway are reflected to be constructed of a 12-inch crushed aggregate base. However, the developer has verbally indicated that both the driveway and parking lot will be surfaced with asphalt millings. Same will be included as a condition of approval to ensure that dust will be suppressed and moreover that gravel will not be tracked onto the City street.

BUILDING

The plan for the proposed garage reflects a single story, gabled roof structure, constructed of metal panels with approximately 1,800 SF of floor area. The building will accommodate both an office and single restroom located within the NW corner of the structure with the balance being comprised of open floor space. Access to the building will be provided by three 10 FT by 12 FT overhead garage doors facing south and a single overhead door on the north side of the structure. Two entryway doors are called out on both the front and rear of the building.

The building structure will be erected upon a concrete slab anchored by a grade beam surrounding the building exterior. The eave height of the proposed garage is approximately 15 FT. The gabled roof will be constructed of steel panels as will the building facades. A stone wainscoting is reflected upon the front facing building façade.

EROSION CONTROL

Erosion control BMPs are proposed to be installed prior to the onset of construction and maintained until the site has been stabilized. The proposed BMPs include the following:

- Silt Fence- Silt fence is proposed to be installed downgradient of the area of site disturbance along the east, west and southern property lines.
- Tracking Pad – A single tracking pad, 20 FT in width, is to be installed at the location of the proposed driveway entrance from Hilltop Drive. The tracking pad will help to prevent construction debris from being deposited along Hilltop Drive.
- Ditch Checks – Hay bales are shown to be staked at the termination points for both of the north-south site drainage swales. The ditch checks will slow surface water flow and stem erosion of ditches until they are stabilized with vegetation.

The plans, Pages 4 and 5, address requirements for the erection, monitoring and maintenance of the erosion control BMPs. It is imperative that the contractor adhere to the requirements as stated within the plans in addition to all City and state requirements. As site grading activities impact less than 1-acre a NOI will not be required pursuant to WDNR NR-151 requirements.

LIGHTING

The proposed project site lighting is minimal and consists of affixing 6 bronze 35-watt LED fixtures to the building exterior. Four fixtures will be installed along the front of the building and two fixtures along the rear facade. The manufactured fixtures are shrouded and constructed to focus light in a downward direction and limit light emittance.

CONCLUSIONS and RECOMMENDATIONS

The site plan submittal supporting the Letkewicz garage building appears sufficient to allow the City of Mayville Plan Commission to conditionally approve the proposed project. Our recommendations for conditions to be incorporated into the approval consist of the following:

- 1) That plans and project details be provided to the City for review inclusive of the following:
 - Signage if same is proposed to be installed within the parcel
 - Landscaping, if same is to be included in conjunction with the project
- 2) That the contractor notifies both the City Utility Director and the Director of Public Works, in advance of the proposed utility construction within the Hilltop Drive ROW, to ensure compliance with City requirements for construction and restoration.
- 3) That both the schedule for erection and maintenance of the erosion control BMPs, as reflected on Pages 4 and 5 of the plans be followed throughout the construction process.
- 4) That both the driveway and parking lot be capped with a minimum of 2-inches of compacted asphalt millings. This measure will eliminate gravel from being tracked onto the street and limit dust during dry weather.
- 5) That the contractor maintains the Hilltop Drive ROW to ensure silt and construction debris are not tracked onto the pavement.
- 6) That City Public Works Department inspect the construction of the proposed driveway entrance onto Hilltop Drive.
- 7) Any other conditions as set forth by the City of Mayville Plan Commission.


The above concludes our review of the plans and specifications for the Letkewicz garage building project. Should either you or representatives of the City Plan Commission have any questions please contact me.


Sincerely,

KUNKEL ENGINEERING GROUP



Don Neitzel, General Manager





GRADING & DRAINAGE PLAN

HJM CONSULTING ENGINEERS, LLC
440 CHALIFOUER ROAD - SUITE 140
Phone: 920/692-5660 Fax: 920/692-6613

RELEASE DATE: BY:

Project Name:
A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A

A



A

A

A

A

A



FINAL - 3/2/2023

C

DRAFTER: JAR
DATE: 3/2/2023
SCALE: 1"=20'
DRAWING NO.

20 0 20 40

20


0

20

40


REVISIONS:	2	PROJECT NUMBER:	100-010
DATE:	07/01/2022	DATE:	07/01/2022
DESCRIPTION:	EROSION CONTROL DETAILS		
<p align="center">Erosion Control Details</p> <p>Standard Detail Drawing Sheet 14 of 21</p>			
<p>Standard Detail Drawing Sheet 15 of 21</p>		<p>Standard Detail Drawing Sheet 16 of 21</p>	
<p>Standard Detail Drawing Sheet 17 of 21</p>		<p>Standard Detail Drawing Sheet 18 of 21</p>	
<p>8E14: Tracking Pad</p> <p>SECTION B-B</p> <p>PLAN VIEW</p> <p>SECTION E-E</p> <p>SECTION F-F</p> <p>Standard Detail Drawing Sheet 19 of 21</p>			
<p>Standard Detail Drawing Sheet 20 of 21</p>			

FINAL SITE PLAN 10/28/22



ST JOHN'S PLAYGROUND

CITY OF MAYVILLE, WISCONSIN



**CITY OF MAYVILLE
VICINITY MAP**



Sheet List Table	
Sheet Number	Sheet Title
C000	Cover Sheet
C100	Existing Conditions
C200	Demolition & Erosion Control Plan
C300	Overall Site Development Plan
C301	Detailed Site Development Plan
C900	Construction Notes
C901	Construction Details
C902	Construction Details

PROGRESS DRAWING

528 BRIDGE ST, MAYVILLE, WI

PROJECT INFORMATION					
PROJECT NUMBER:	0000-C000-0101	ISSUE NO.:	1	DATE:	03-30-2023
DRAWN BY:	CW	REVISIONS:		CHECKED BY:	RGR
APPROVED BY:	DSR	SCALE:	AS SHOWN		

COVER SHEET	
SHEET TITLE:	

C000

GR^EEF

One Honey Creek Corporate Center
125 South 54th Street, Suite 401
Milwaukee, WI 53214-1489
414/258-1500
414/259-0373 Fax

www.grefusa.com

C CONSULTANTS:

PROJECT TITLE:
ST. JOHN'S PLAYGROUND

ISSUE:
NO. DATE REVISIONS BY

PROGRESS DRAWING


520 BRIDGE ST, MAYVILLE, WI

PROJECT INFORMATION
PROJECT NUMBER: 2022-0187-10
DATE: 03-30-2023
DRAWN BY: CW
CHECKED BY: RCR
APPROVED BY: DRR
SCALE: AS SHOWN

SHEET TITLE:
EXISTING CONDITIONS

SHEET NUMBER:

C100



NOTES: Surveyed with Minnesota state-of-the-art 100-DT75, showing the true horizontal distances and true vertical elevations. All surveying work was conducted by professional surveyors. The surveyor responsible for this work is not responsible for any errors or omissions in the work or data contained on this drawing. This drawing is the property of GR^EEF, Inc. and is to be used only for the purpose intended. Any unauthorized use, distribution, or copying of this drawing is prohibited by law. The surveyor responsible for this work is not responsible for any errors or omissions in the work or data contained on this drawing. This drawing is the property of GR^EEF, Inc. and is to be used only for the purpose intended. Any unauthorized use, distribution, or copying of this drawing is prohibited by law.

DISCLAIMER:



One Haley Creek Corporate Center
125 South 54th Street, Suite 401
Milwaukee, WI 53214-1459
414/259-1500
414/259-0153 fax

www.grgefusa.com

CONSULTANTS:

LEGEND

- PLAYGROUND SURFACE REMOVAL
- X-SIDEWALK REMOVAL
- SCE-STONE CAPSTANCH ENTRANCE
- EROSION MATTING
- SLT FENCE
- INLET PROTECTION

PROJECT TITLE:
C ST. JOHN'S PLAYGROUND


PROGRESS DRAWING


520 BRIDGE ST, MAYVILLE, WI

PROJECT NUMBER: 2022-0197.10
DATE: 03-30-2023
DRAWN BY: CW
CHECKED BY: RCR
APPROVED BY: DSR
SCALE: AS SHOWN


NO. DATE REVISIONS BY

ISSUE:
A SHEET TITLE:
DEMOLITION & EROSION CONTROL
PLAN
SHEET NUMBER:
C200





0 20' 40' 80'
SCALE: 1" = 40'




GROVE STREET


BRIDGE STREET

NORTH WALNUT STREET

DAYTON STREET

NOTES: All dimensions shown are U.C.D. (True Horizontal).
Dimensions are in feet unless otherwise indicated.
Horizontal dimensions are measured from the centerline of the railroad tracks.
Vertical dimensions are measured from the bottom of the railroad tracks.
Elevations are in feet above sea level.
All dimensions are approximate.
This drawing is the property of GR&EF, Inc. It is to be used only for the project described on the title block.
Any unauthorized copying or distribution of this drawing is prohibited by law.
Copyright © 2023 GR&EF, Inc. All rights reserved.
DISCLAIMER: This drawing is for planning purposes only and is not a final engineering drawing. It is the responsibility of the user to verify all information contained herein against applicable codes and regulations. The user is responsible for any errors or omissions and shall be liable for any damages resulting from the use of this drawing. The user agrees to indemnify and hold GR&EF, Inc. harmless from any claims, losses, or expenses arising from the use of this drawing.





PROGRESS DRAWING

INLET PROTECTION, TYPE B
(WITHOUT CURB BOX)

N.T.S.

02 SCALE

01 SILT FENCE

N.T.S.

SCALE

03 STONE CONSTRUCTION ENTRANCE

N.T.S.

SCALE

04 EROSION MATTING

N.T.S.

SCALE

N.T.S.



SCALE

PROJECT TITLE:

ST. JOHN'S PLAYGROUND

PROGRESS DRAWING


520 BRIDGE ST, MAYVILLE, WI
NO. DATE REVISIONS BY





On-Harley Creek Concrete Center
125 South 8th Street, Suite 401
Milwaukee, WI 53214-4469
414 / 789-1500
414 / 759-0057 FAX
www.grc-usa.com

C CONSULTANTS:
[REDACTED]



Draft for Discussion Purposes - Preliminary Values

Clark Street Residential Development

Conceptual Budget

Town House Concept

Projected Revenue

Lot	Zoning	Land Value	Residential Value	Total Value	Projected Annual Taxes
1	1 or 2 Family	\$30,000	\$350,000	\$380,000	\$5,662.00
2	1 or 2 Family	\$40,000	\$350,000	\$390,000	\$5,811.00
3	1 or 2 Family	\$40,000	\$350,000	\$390,000	\$5,811.00
4	1 or 2 Family	\$40,000	\$350,000	\$390,000	\$5,811.00
5	1 or 2 Family	\$45,000	\$350,000	\$395,000	\$5,885.50
6	1 or 2 Family	\$35,000	\$350,000	\$385,000	\$5,736.50
7	1 or 2 Family	\$30,000	\$350,000	\$380,000	\$5,662.00
8	1 or 2 Family	\$30,000	\$350,000	\$380,000	\$5,662.00
9	3 Unit Rowhouse	\$40,000	\$900,000	\$940,000	\$13,969.55
10	3 Unit Rowhouse	\$40,000	\$900,000	\$940,000	\$13,969.55
11	3 Unit Rowhouse	\$40,000	\$900,000	\$940,000	\$13,969.55
12	3 Unit Rowhouse	\$40,000	\$900,000	\$940,000	\$13,969.55
13	3 Unit Rowhouse	\$40,000	\$900,000	\$940,000	\$13,969.55
Totals		\$490,000	\$7,300,000		\$115,888.74

Assume a five year build out, 17 year TIF
12 Years at full taxes \$1,390,664.85

Projected Development Costs

Land Purchase	\$150,000
Legal	\$14,000
Environmental Survey	\$3,000
Soil Testing	\$14,000
Survey work	\$26,000
Engineering for PUD	\$60,000
Road and Utility Construction	\$651,644
Water Connections and Impact Fees	\$19,500
Project Management	\$75,000
Five Years of Holding Costs	\$40,625
Sale Commissions	\$29,400
	\$1,083,169
Development Fees - 25%	\$122,500
Total Development Costs	\$1,205,669


City Reimbursed Cost

Road Construction	\$651,644
PUD Engineering	\$60,000
Soil Testing	\$14,000
Hold Costs	\$40,625
Legal	\$14,000
Water Connections and Impact Fees	\$19,500
Survey Work	\$26,000
	\$825,769

Projected Return

Revenue	\$490,000
Total Cost	(\$1,205,669.40)
City Reimbursement	\$825,769
Net to Developer	\$110,100.00

Revised Site Layout Single Family & Townhouses



(8) 1 or 2
Family
Lots 1-8

(5) 3-Unit
Townhouse
Lots 9 - 13

Draft for Discussion
Purposes - Preliminary
Values

Clark Street Residential TIF Calculations

Lot	Zoning	Land Value	Residential Value	Total Value	Projected Annual Taxes
1	1 or 2 Family	\$45,000	\$350,000	\$395,000	\$5,870.18
2	1 or 2 Family	\$30,000	\$350,000	\$380,000	\$5,647.26
3	1 or 2 Family	\$30,000	\$350,000	\$380,000	\$5,647.26
4	1 or 2 Family	\$30,000	\$350,000	\$380,000	\$5,647.26
5	1 or 2 Family	\$30,000	\$350,000	\$380,000	\$5,647.26
6	1 or 2 Family	\$30,000	\$350,000	\$380,000	\$5,647.26
7	1 or 2 Family	\$40,000	\$350,000	\$390,000	\$5,795.88
8	1 or 2 Family	\$50,000	\$350,000	\$400,000	\$5,944.49
9	1 or 2 Family	\$45,000	\$350,000	\$395,000	\$5,870.18
10	1 or 2 Family	\$45,000	\$350,000	\$395,000	\$5,870.18
11	1 or 2 Family	\$35,000	\$350,000	\$385,000	\$5,721.57
12	1 or 2 Family	\$35,000	\$350,000	\$385,000	\$5,721.57
Totals		\$445,000	\$4,200,000		\$69,030.37

Assume a five year build out, 17 year TIF

12 Year at full taxes \$828,364.44

Projected Development Costs

Land Purchase	\$150,000
Legal	\$14,000
Environmental Survey	\$3,000
Soil Testing	\$14,000
Survey work	\$24,000
Engineering	\$15,000
Road and Utility Construction	\$651,644
Project Management	\$75,000
Five Years of Holding Costs	\$40,625
Water Connections and Impact Fees	\$19,500
Sale Commissions	\$26,700
	\$1,033,469
Development Fees	\$111,250
Total Development Costs	25%
	\$1,144,719

City Reimbursed Cost

Holding Costs	\$40,625
Road Construction	\$651,644
PUD Engineering	\$15,000
Soil Testing	\$14,000
Hold Costs	\$40,625
Legal	\$14,000
Water Connections and Impact Fees	\$19,500
Survey Work	\$24,000
	\$819,394

Projected Return

Revenue	\$445,000
Total Cost	(\$1,144,719.40)
City Reimbursement	\$819,394
Net to Developer	\$119,675.00



Draft for Discussion Purposes - Preliminary Values


Leona Street – (3) Vacant Parcels

- 0.6 acres +/- each
- Zoned R-B-1 Mixed One & Two Families



Option #1

- 6 Duplexes – 2 units per 0.6 acres
- 2400 SF units – 2 story 30'x40'
- Current Zoning Allows



Option #2

- 12 Duplexes – 2 units per 0.3 acres
- 2400 SF units – 2 story 30'x40'
- Requires (3) land divisions



Leona Street - 3 Vacant Parcels Zoning Map & Setbacks

Current Zoning Code:

Lot area and width. Lot area and width requirements are as follows:

(1) Minimum lot area: 7,000 square feet.

(2) Minimum lot width: 66 feet.

F. Building height and area. Building height and area requirements are as follows:

(1) No building or parts of a building shall exceed 35 feet in height.

(2) No single-family dwelling shall be less than 750 square feet of living area.


(3) No structure converted to a two-family occupancy shall occupy less than 750 square feet of ground area for the principal dwelling unit and 600 square feet of living area for the converted unit.

G. Yards. Yard requirements are as follows:

(1) Minimum street yard: 25 feet.

(2) Minimum side yard: 10 feet.

(3) Minimum rear yard: 40 feet.



Proposed Land Division (6 lots total)

(1) Lot Area 0.3 acres or 13,095 square feet

(2) Lot Width: 100 feet

(3) Height: < 35' likely 30' max, but built in hillside

(4) Area: >750 SF

(5) All yard set backs met.

ZONING DISTRICT

R-A SINGLE FAMILY

R-B SINGLE FAMILY

R-B-1 MIXED ONE AND TWO FAMILY

R-C TWO FAMILY

RM MULTIPLE FAMILY


366 & 36/ Park Lane

- Full Duplex
- 0.25 acre lot



362 & 364 Park Lane

- Half Duplex Each
- 0.124 & 0.134 acre lots




Parcels Feature Information

gispin:	25112162341052
Owner:	RICHARD B PICCHOTTI
Co-Owner:	
Mailing Address 1:	362 PARK ST
Mailing Address 2:	
Mailing City:	MAYVILLE
Mailing State:	WI
Mailing Zip:	53050
City Address:	362 PARK ST
Report	Landshark



336/338 & 344/346 Nelson Road

- Half Duplex Each
- 0.156 – 0.209 acre Each



Google